ADDENDUM NO. 04

Date: March 18, 2024

Issued by: Sacramento City Unified School District

Project: **Project #: 0004-468**
Alice Birney Waldorf TK-8 Campus Renewal

This addendum shall supersede the original Information, attachments, and specifications regarding Project No. 0004-468 where it adds to, deletes from, clarifies or otherwise modifies them. All other conditions and any previous addenda shall remain unchanged.

AD04.01 – Pre-bid RFI response:

RFI 5 Tw 11.04 -0 0 11onsMP <</MCID

SECTION 09 67 23 ±TROWELED EPOXY FLOORING WITH CEMENTIOUS UNDERLAYMENT ± ADDENDUM # 4

PART 1 ±GENERAL

1.1 SUMMARY

A. Section Includes:

G. NFPA 101 ±Life Safety Code

H. NFPA 253 ±Standard Method of Test for Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source

I. SMAQMD ±Sacramento Metropolitan Air Quality Management District Regulations.

1.3 SUBMITTALS

A. Action Submittals:

1. Product Data / Technical Data for each system component and accessory item, including application instructions and general recommendations for waterproof flooring.

a. Material certificates signed by manufacturer certifying that the polyacrylate resin composition underlayment complies with requirement specified herein.

2. Certified copies of Field Quality Assurance Test Reports.

3. Shop Drawings showing traffic areas that will receive non-slip finish and equipment and fixture layout that will receive standard smooth finish.

4. Samples:

a. Provide physical samples of full line of color options and textured finishes for epoxy flooring.

b. Provide 2-1/2" x 4" samples of underlayment.

B. Information Submittals:

1. 0 D Q X I D F W X U H U ¶ V , Q V W D O O D W L R Q , Q V W U X F W L R Q V

2. Certificates of Compliance regarding specified performance requirements.

C. Closeout Submittals: Manufacturer's Maintenance Instructions.

1.4 QUALITY ASSURANCE

A. Flooring system components shall be compliance with VOC content limits in SMAQMD.

B. Installed flooring system shall have ASTM C1028, Coefficient of Friction, as follows.

1. Dry/Level Surfaces: 0.6, minimum.

2. Wet/Sloped Surfaces: 0.8, minimum.

C. Installed flooring system shall be CBC Section 803.1, Class A interior finish with the following surface burning characteristics.

1.6 PROJECT REQUIREMENTS

A. Do not install flooring when temperature is below 60°F or above 90°F.

B. Maintain this temperature range, 24 hours before, during and 72 hours after installation of flooring.

C. Restrict traffic from area where flooring is being installed or is curing.

1.7 WARRANTY

A. Manufacturer shall warrant installed flooring to be and to remain free from defect for a minimum period of one (1) year (and up to 3 years depending on manufacturer and product) from Date of Substantial Completion. Upon written notice from Owner, manufacturer shall promptly, without cost, and with least practicable inconvenience to Owner correct such defects.

B. Evidence of defect in material, installation or both shall be delamination from substrate or degradation of surface finish individually or in combination.

PART 2 ±PRODUCTS

2.1 MANUFACTURERS / PRODUCTS ±TROWELED EPOXY FLOORING

A. Products of the following manufacturers form the basis of design and quality intended for this Project.

1. Dex-O-Tex, manufactured by Crossfield Products Corp., Compton, CA.

2. Stonhard, Inc., Maple Shade, NJ

3. Tera-Lite, Inc., San Jose, CA.

4. Sherwin Williams.

5. Or equal, approved in accordance with Division 01 requirements for substitutions.

B. Provide epoxy flooring system that meets or exceed the listed minimum physical property requirements when tested according to the referenced standard test method in parentheses.

1. Tera-Gem III DQ, manufactured by Tera-Lite:

a. Thickness: 1/4 inch.

b. Compressive Strength (ASTM C579): 10,500 psi.

c. Tensile Strength (ASTM C307): 2,500 psi.

d. Flexural Strength (ASTM C580): 4,700 psi.

e. Water Absorption (C413): 0.25% max.

f. Surface Hardness (ASTM D2240): Shore D ±83.

g. Abrasion Resistance (ASTM D4060): 1000 cycles, wt. loss (gm), .037gm.

h. Impact Resistance (MIL-D-3134F, Section 4.7.3): No cracking or delamination at 16 ft. lbs.

i. Adhesion Impact Resistance (Gardner Impact Tester): No chipping, cracking, or delamination and not more than 0.014" indentation Adhesion (A.C.I. Comm. No. 503.1): 400 psi (100% failure in concrete)

j. Electrical Conductivity (NFPA 56A): Di-electric

k. Flammability (ASTM E635): Self-extinguishing

l. Colors: As selected by Architect and Owner I U R P P D Q X I D F W X U H U ¶ V range of available colors. Grouted with selected variegated aggregates, top coated with clear finish coat.

m. Quartz decorative finish: ColorQuartz for Tera-Gem III DQ, color or blend as selected by Architect.

n. Primer: Two-component moisture tolerant epoxy primer.

o. Basecoat: Three-component, troweled polymer composite consisting of epoxy resin, curing agent, and choice of colorquartz, dolo aggregate b 0.00e00009452 792-4(o(nt)(i)-4(ce)4(of)4( )5(co)11(l)-4(orq)13(ua)10(r)3

3. Contaminated Concrete Surfaces: Clean concrete surfaces by sandblasting, steel shot-blasted, scarified, water blasted, or other approved technique by the flooring manufacturer.

F. Repair minor defects. The substrate was prepared under this section; remove ridges, fill depressions and repair cracks as required by floor coating manufacturer to execute specified warranty.

1. Apply, trowel and float filler to leave a smooth, flat, hard surface, free of bumps or depressions of any size.

2. Prohibit traffic from area until filler is cured.

G. Vacuum clean substrate.

H. Apply primer as recommended by the materials manufacturer.

I. , Q V W D O O Z D W H U S U R R I P H P E U D Q H S H U , If Damp cured W X U H U ¶ V U

3.3 INSTALLATION

A. Cementitious Underlayment

2q 0.00000912 0 612 792 re W* n BT /F1 10.56 Tf 1 0 0 1 144.02 553.1838229.0224.3.03 Tm 0 G [( )] TJ ET Q EMC /Sp