Business Services
Contracts Office
5735 47th Avenue z Sacramento, CA 95824
(916) 643-2464
Jesse Castillo, Interim Chief Business Officer
Robert Aldama, Purchasing Manager II

ADDENDUM NO. 1.0

Date: 08/15/2023

Issued by: Sacramento City Unified School District

Project: Project #: 0163- 464
John Cabrillo ES Telecenter Upgrade Project

This addendum shall supersede the original Information, attachments, and specifications regarding Project No.0163-464 where it adds to, deletes from, clarifies or otherwise modifies them. All other conditions and any previous addenda shall remain unchanged.

Part A – Bidding and Contract Requirements

AD 1.10:

Question: How to keep the analog speakers operating during the transition.

Answer : Reference Sheet E1.2 – section “Phasing”-

1. The contractor shall install the #tcc2000, #tcc2033, and #tcc2055 at the head end and #tcc2045 in the office. Temporarily mount equipment in the existing MDF or on the Existing backboard during the transition if needed. Program a nd test the head end equipment and verify it functions as intended.
2. Remove all analog head end equipment except the Amplifiers. Provide and install two Rauland Borg #tcc2022 Zone paging modules to convert the IP signals to analog Signals. Connect the output of the modules to the existing amplifiers and test the system. The system shall be functional b efore the next school day.
3. Provide, install, program, and test all switches, ups, patch Panels, and patch cords.
4. Convert one wing at a time from analog to IP. Disconnect All existing speakers and clocks in the wing being converted at the start of the conversion. Install new cables, clocks, and speakers and/or horns. All cables shall be tested before Use. Perform all programming. Test the system. The system Shall be functional before the next school day.
5. Once the entire school is converted from analog to IP Disconnect and remove all amplifiers and unused 66- blocks and analog wiring. Return the #tcc2022 zone paging Modules to the district. Relocate any headend equipment Installed outside of the head end equipment rack to the Head end equipment rack. Provide final programming and System testing.

Also reference Sheet E1.2 – section “Clock, Speaker, And Horn Legend” -



AD 1.12:

Question: During the site walk, it was noticed that certain MDF/IDFs may have an adequate

AD 1.13:

Question: On sheet E1.2, the plans call for new UPS battery backups to be contractor furnished and installed (Part #'s SU1000RTXLCD2U and SU1500RTXLCD2U). On page 38 of the specifications, it calls for